

Annerxure One

Name of Work : Renovation of IPP-4 Building at Helna Susunia P.H.C.
Ref. No. : CMOH/ H.S. P.H.C./2011/01

Date :

Time of Completion : 30 Days

NOTE :-

- i) All the quoted rates should be firm.
- ii) All the items and work should be approved as per P.W.D. schedule effective from 1st August, 2010 or as per Engineer-in-charge of DPMU, Health & Family Welfare Samity, Bankura.
- iii) Measurement should be as per actual site work.

Somik Shannigrahi

Assistant Engineer
National Rural Health Mission
District Health and Family Welfare Samity
Health and Family Welfare Department
Govt. of West Bengal

S/L No	Description of Item	Unit	Quantity	Rate(Rs/-)	Amount in Rs/-
1	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and any floor including removing rubbish within a lead of 75m as directed	Sq.M.	116.56		
2	Plaster(to wall,floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).(Excluding cost of chipping over concrete surface) (ii) with 1:4cement mortar (b) 15 mm thick plaster	Sq.M.	116.56		
3	Synthetic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer (as per manufacturers specification) including cleaning and smoothing of surface. Two Coats	Sq.M.	388.53		
4	Labour for taking out door and window frame including shutter for repair or replacement of different parts of the frame & refixing the same including mending good all damages complete. (concrete and brick work for mending damage will be paid separately) (a)Upto area 2.5 sq.m Nos of WINDOW-11	Sq.M.	7.03		
5	Supplying, fitting and fixing M.S. clamps for door and window frame made of flat bent bar, end bifurcated with necessary screws etc. by cement (1:2:4) as per direction .(Cost of concrete will be paid separately) (a) 40 mm x 6 mm, 250 mm length	Each	58		
6	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. For WINDOW (iv) 75 mm x 47 mm x 1.70 mm	Each	96		
7	Iron socket bolt of approved quality fitted and fixed completed. For WINDOW (b) 100mm long x 10mm dia bolt For DOOR (d) 225 mm long x 10 mm dia bolt	Each	36 11		
8	Anodised aluminium decorative handle (hexagonal/fluted) of approved quality fitted and fixed complete. For DOOR (i) 150 mm plate x 10 mm dia rod x 60 mm hexagonal / fluted.	Each	11		
9	(A) Iron door ring of approved quality fitted with nut and washer completed. For WINDOW (i) 50 mm dia.	Each	32		
10	(i) Iron Hasp bolt of approved quality fitted and fixed complete(oxidised) with 16mm dia rod with centre bolt and round fitting . (b 250 mm long(for DOOR)	Each	7		

Samik Shannigrahi
 Assistant Engineer
 National Rural Health Mission
 District Health and Family Welfare Samity
 Health and Family Welfare Department
 Govt. of West Bengal

S/L No	Description of Item	Unit	Quantity	Rate(Rs/-)	Amount in Rs/-
11	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame excluding cost of concrete, Iron butt Hinges and M.S clamps .(The quantity should be corrected upto three decimals.) (h) Neem, jam, jackfruits (For WINDOW)	Cu.M.	0.546		
12	Panel shutters of door and widow, as per design (each panel consisting of single plank with out joint), including fitting and fixing the same in position but excluding the cost of hinge and other fittings. In Ground Floor: (In case of non supply of single plank , panel rate of 20% will be made) (iii) 35 mm thick shutters with 19 mm thick panel of size 30 to 45 cm (b) Sishu, Gamar,.....	Sq.M.	21.93		
13	(a) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	Sq.M.	156.55		
	(b) Priming one coat on steel or oter metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	Sq.M.	34.46		
14	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface if necessary: (a)On timber surface With super gloss(hi gloss) (iv) Two coats (with any shade except white) With super gloss(hi gloss)	Sq M	156.55		
	(b) On steel surface or other metal surface (iv) Two coats (with any shade except white)	Sq.M.	34.46		
15	Easing and oiling, cleaning collapsible gate and repairing to locking arrangements.	Sq.M.	3.15		
16	Taking out iron hinges and fitting, fixing the same with new steel screws. (e) 100 long butt hinge. (for DOOR)	Each	42		
17	Square or hexagonal mesh netting made with 18 B.W.G. galvanised wire, fitted and fixed complete as per design (excluding the supporting framework but including local sal wood battens of size 37.5mm x 25mm). (a) 19 mm mesh (For WINDOW)	Sq.M.	20.00		
18	Ordinary Cement Concrete(mix 1:2:4) with graded stone chips (20mm. Nominal size) excluding shuttering and reinforcement,if any,in ground floor as per relevant IS codes (d) With local hard blackstone variety chips (crusher broken)	Cu.M.	0.75		
19	Taking out M.S. or W.I. Grills from wooden frame including cutting lugs from masonry wall and refitting the same and mending good damages after repairs . (Excluding the cost of necessary repair of damages) or doing any other necessary works.	Each	11		
				Total	

Rupees :

Sanku Shannigrahi
Assistant Engineer
National Rural Health Mission
District Health and Family Welfare Samit
Health and Family Welfare Department
Govt. of West Bengal